

BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/03/2014-15, Date:31.10.2014.

ITEM NO: 42

SCHEDULE-B

NAME OF WORK: Improvements drains & Re-Asphalting to roads at Diffence Colony in Ward No.14, Bagalagunte.

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor G N RAMESH	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods Complete as per specification and direction of Engineer-in-charge of the work	Cum	564.6	75.6	Rupees Seventy Five and Sixty Paise Only
2	Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications with all leads and lifts etc., Complete as per specification and direction of Engineer-in-charge of the work	Sqm	1199	4.48	Rupees Four and Forty Eight Paise Only
3	Providing, laying, spreading and compacting graded stone aggregates to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. Specification No. 406 with all leads and lifts etc., Complete as per specification and direction of Engineer-in-charge of the work	Cum	359.7	1438.56	Rupees One Thousand Four Hundred Thirty Eight and Fifty Six Paise Only
4	Providing and applying primer coat with S.S. Bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.6 kg / sqm using mechanical means complete as per specifications, with all leads and lifts etc., Complete as per specification and direction of Engineer-in-charge of the work	Sqm	1199	34.56	Rupees Thirty Four and Fifty Six Paise Only

Signature of the Contractor

EXECUTIVE ENGINEER-4
ROADS & BRIDGES DIVISION,
BANGALORE-560 010


Executive Engineer

5	Providing and laying bituminous macadam on prepared surface with crushed coarse aggregates as per design mix formula for base / binding course including loading of aggregates with F.E. loader, hot mixing of stone aggregates and bitumen in hot mix plant 40 tonne capacity, transporting the mixed material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by power roller to achieve the desired density, 50/75mm compacted thickness with 3.3% bitumen but excluding the cost of primer/tack coat with lead incl. cost of all materials, labour, HOM of machineries complete as per specifications with 80/100 grade bitumen using 40/60TPH capacity H.M.P with sensor paver Gr II (50/75mm) with 3.3% VG-30 Bitumen Complete as per specification and direction of Engineer-in-charge of the work	Cum	59.95	6957.36	Rupees Six Thousand Nine Hundred Fifty Seven and Thirty Six Paise Only
6	Providing and applying tack coat on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (exlcuding cleaning of road surface) including cost of all materials, labour, HOM of machineries Complete as per specification and direction of Engineer-in-charge of the work	Sqm	5995	18.74	Rupees Eighteen and Seventy Four Paise Only
7	Providing and laying semi dense bituminous concrete 25 - 30mm compacted thickness with 5% bitumen with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 508 complete in all respects with 80 / 100 grade bitumen with all leads and lifts etc., Complete as per specification and direction of Engineer-in-charge of the work	Cum	179.85	9851.76	Rupees Nine Thousand Eight Hundred Fifty One and Seventy Six Paise Only
8	Carraige of Mixed Materials above 15 Km beyound 10Km to 15 Kmslead at Complete as per specification and direction of Engineer-in-charge of the work	Cum	179.85	73.5	Rupees Seventy Three and Fifty Paise Only
9	Providing and laying in position plain cement concrete of mix M1:2:4 with cement @240 kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing Complete as per specification and direction of Engineer-in-charge of the work	Cum	40.8	5047.6	Rupees Five Thousand Forty Seven and Sixty Paise Only

Signature of the Contractor

 EXECUTIVE ENGINEER
 ROAD & BUILDING DIVISION
 BANGALORE-560 010


 Executive Engineer

10	Supplying and fixing precast reinforced concrete slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface etc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials. Complete as per specification and direction of Engineer-in-charge of the work	Sqm	306	1600.0	Rupees One Thousand Six Hundred Only
11	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Complete as per specification and direction of Engineer-in-charge of the work	Cum	479.6	78.24	Rupees Seventy Eight and Twenty Four Paise Only

Signature of the Contractor

~~EXECUTIVE ENGINEER~~
~~KADUR, DEPT. DIVISION,~~
BANGALORE-560 010

Executive Engineer,
Dasarahalli Division,